Abstract of quantities for constructing a Police Station at Ananthapur, Sagar Taluk.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Earthwork excavation and filling in basement ... | C.yd. | 54 |
| 2 | Metal concrete ... | C.ft. | 390 |
| 3 | Cut laterite brick in mortar ... | " | 2005 |
| 4 | Do clay ... | " | 1844 |
| 5 | Do mortar coping for compound wall with pointing, etc., complete. | R.ft. | 69 |
| 6 | Burnt stone slabs 4" thick dressed and fixed ... | S.ft. | 187 |
| 7 | Teakwood doors with iron bars clamps, etc., complete for lockup. | " | 49 |
| 8 | Honneywood battened doors with iron clamps, etc. ... | " | 87·75 |
| 9 | Do battened windows 1/4 glazed with iron bars | " | 35 |
| 10 | Do ventilators with expanded metal ... | " | 11 |
| 11 | Honney wood work wrought and put up ... ... | Cft. | 61·2 |
| 12 | Roofing with 1st class Mangalore tiles on teak reepers ... | Sqr. | 11·20 |
| 13 | Ridge tiles set in mortar ... ... ... | R.ft. | 40 |
| 14 | Chunam borders 9" x 9" over roof ... ... | " | 48 |
| 15 | Teakwood ceiling ½" thick plank ... ... | S.ft. | 210 |
| 16 | Chunam plastering ... ... ... ... | S.qr. | 23·85 |
| 17 | Do pointing ... ... ... ... | " | 19·79 |
| 18 | Honney wood eave board ... ... ... ... | R.ft. | 136 |
| 19 | Wood oiling ... ... ... ... ... | S.qr. | 6·00 |
| 20 | Tarring ... ... ... ... ... | " | 3·00 |
| 21 | Jungle wood railings ... ... ... | R.ft. | 52 |
| 22 | Flooring with 1st class Mangalore tiles over 3" concrete and cement pointing. | S.qr. | 3·92 |
| 23 | Flooring with Cuddapah slabs over 3" concrete and cement pointing. | " | 1·53 |
| 24 | Jangle wood gate with iron fittings, etc., complete ... | S.ft. | 15 |
| 25 | Chacolate painting ... ... ... ... | S.qr. | 7·27 |
| 26 | Constructing masonry V shaped drains alround ... | R.ft. | 100 |
| 27 | Flooring with gravel in open yard ... ... | C.yd. | 12 |
| 28 | Jungle wood finils ... ... ... ... | E | 2 |
| 29 | Do pendents ... ... ... | " | 4 |
| 30 | Providing honney wood pillars with capital and base ... | " | 2 |
| 31 | Constructing latrne seats and drain pipes ... ... | Lump sum | 1 |
| 32 | Clearing site and levelling ground ... ... ... | " | " |

S. MUTHUSWAMI IYER,
*Executive Engineer.*

## MISCELLANEOUS DEPARTMENTS.

### GOVERNMENT OF MYSORE: ELECTRICAL DEPARTMENT.

*Dated 7th December* 1927.

Attention of the public is invited to the detailed notification published in the *Mysore Gazette* dated the 15th December 1927, Part VI, inviting tenders for the purchase of 20 tons of Solid Hard Drawn Bare Copper Wire. Tenders should reach the office of the undersigned on or before 12 noon of the 14th January 1928 Earnest money required is Rs. 500. Copies of the notification will be sent on application.

B. D. NATH,
For *Chief Electrical Engineer.*

### OFFICE OF THE DIRECTOR OF INDUSTRIES AND COMMERCE.

The public are hereby informed that it is arranged to hold an auction sale of weaving accessories attached to the Government Weaving Factory, Bangalore, at the premises of 'Anandasrama', Bangalore, from 15th to the 23rd December 1927 (from 10 A.M. to 12 noon every day).

The stock for auction comprises of loom parts, old and new, sizing machines, winding machines and parts thereof, jacquard machines twisting machines, raw filature silk, coloured silk, cotton and shed materials, etc., etc.

The shed materials will be auctioned only on the 23rd instant by the Director of Industries and Commerce in Mysore, Bangalore.

C. RANGANATHA RAO SAHEB,
*Director.*